BANGALORE DIVISION.

Dated 15th March 1917.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 4 P.M., Monday, 2nd April 1917, for restoring Bheemanakere, Minor Tank of Bangalore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1917.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred in Currency or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Challahalli-Bheemanakere Minor Tank of Bangalore Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Restoring Challahalli-Bheemanakere Reg. No. 234 (Minor Tank), Bangalore Taluk.

Items of work	Per	Quantity
Bund—		
(1) Clearing seat of bund	Grade	24
(2) Earthwork to bund	C. yd.	3,430
(3) Turfing the slopes of bund	S. yd.	4,356
(4) New stone revetment...	C. yd.	1,218
(5) Providing grade stones as per details	Each	25
(6) Do index stones do	"	25
(7) Do date and Register number stones as per details	"	1
(8) Do B. M. stones as per details	"	2
Sluice—		
Repairing the existing one or after opening if found necessary to construct a new sluice.	Lump sum	Rupees.
Weirs—		
(1) To provide burnt stone slabs over body wall where not available to a length of 20 feet.	S. ft.	30
(2) Petty repairs such as plastering, etc.	Lump sum	Rupees.
(3) Extending the weir from 52 feet to 172	"	"

Notification dated 7th March 1917.

Grass grown in the catchment area of Sankey's Reservoir, Bangalore, will be sold by public auction, on 31st instant, at 8 A.M., at the tank site, by the Assistant Engineer, Head Quarters Range, Bangalore.

The highest bidder will have to pay one-fourth of the amount at once and balance within a week from the date of auction, failing which the produce will be reauctioned and the difference in the amount of realization will be recovered from the original purchaser.

The lease is for one year only to the 30th June 1918.

C. VIJAYARANGUM NAIDU,
Executive Engineer.

MYSORE DIVISION.

NOTICE.

The travellers' bungalow at Nelligere and Nagamangala in the Nagamangala Taluk are closed for three weeks from the date of this notice as the buildings and out houses attached hereto are under repairs.

Y. ASVATHANARAYANA RAO,
Executive Engineer.